

Proposed Kai Tak Development – Infrastructure at North Apron Area of
Kai Tak Airport – Stage 5 Infrastructure Works

- (i) construction of a dual 2-lane road and three single 2-lane roads approximately 1600 metres (m) long in total and associated footpaths;
- (ii) construction of footpaths approximately 1100 m long in total connecting the associated footpaths in item (i) above;
- (iii) construction of a pair of single-lane slip roads approximately 350 m long in total connecting the dual 2-lane road in item (i) above with the existing flyovers K72 and K73 respectively;
- (iv) construction of a subway approximately 150 m long across Prince Edward Road East and the dual 2-lane road in item (i) above;
- (v) permanent closure and conversion of sections of the existing roads into the roads and/or footpaths in items (i), (ii) and (iii) above;
- (vi) permanent closure and conversion of a section of the existing amenity area into footpath;
- (vii) permanent closure and demolition of sections of an existing road and an existing subway;
- (viii) temporary closure and reconstruction of sections of the existing roads; and
- (ix) ancillary works including construction of lifts, staircases and vehicular run-ins; as well as drainage, water, utility and landscaping works.

Ends