

Proposed Kai Tak Development - Stage 2 Infrastructure Works for Developments at  
the Southern Part of the Former Runway

- (i) construction of mainly dual 2-lane district distributor roads of about 1700 metres (m) long in total and associated footpaths;
- (ii) construction of single 2-lane access roads of about 590 m long in total including a vehicular underpass and associated footpaths;
- (iii) construction of footpaths of about 410m long connecting to the proposed associated footpaths in (i) and (ii);
- (iv) construction of noise barriers, vertical noise barriers integrated with landscaped deck structure and with provision for pedestrian crossings, and overhanging vertical noise barriers integrated with landscaped deck structure of about 1100 m long in total along the roads in (i) (subject to detailed design);
- (v) construction of landscaped deck structure integrated with noise barriers in (iv) of about 1400 m long above the roads in (i) (subject to detailed design);
- (vi) permanent closure and conversion of sections of existing roads into the roads and/or footpaths in (i), (ii) and (iii);
- (vii) permanent closure and demolition of sections of existing roads;
- (viii) temporary closure and reconstruction of sections of existing roads; and
- (ix) ancillary works including construction of vehicular run-ins, drainage pipes and outfalls, as well as water mains, sewerage, utilities, lifts, staircases and landscaping works.

Ends